Holdbacks shall be left bare and be provided as shown on the approved shop drawings. Holdbacks shall be filled with cement mortar after joint completion per AWWA C205.
 Defective linings as identified in AWWA C205 shall be removed from the pipe wall and shall be replaced to the full

centrifugally and conforming with AWWA C205.

- thickness required. Defective linings shall be cut back to a square shoulder in order to avoid feather edged joints.

 4. Fittings shall be cement-mortar lined per AWWA C205. Pipe and fittings too small to cement-mortar line may be lined
- with AWWA C210 epoxy or AWWA C222 polyurethane.

 5. Cement-mortar lining shall be kent moist during storage.