

Area Served		Supply		Return		Pressurization	Remarks
Roon Name	Area M ²	Tag No.	Total CFM	Tag No.	Total CFM	CFM	
Office	20.55	SD-4	600	RLBG-2	500	100	
Office	16.80	SD-3	400	RLBG-1	300	100	
Office	17.10	SD-3	400	RLBG-1	300	100	
Male Waiting	26.12	SD-3	1,000	RLBG-2	900	100	
Female Waiting	15.51	SD-3	500	RLBG-2	400	100	
Corridor	144.04	SD-3	1,600	RD-3	900	700	
Office	9.50	SD-3	500	RLBG-2	400	100	
Office	9.86	SD-3	500	RLBG-2	400	100	
Accoustical & Vis	18.17	SD-4	600	RLBG-2	500	100	
Visible Propagation	37.17	SD-3	1,500	RLBG-2	1,400	100	
Picturing Studio	30.77	SD-3	1,000	RLBG-2	900	100	
Toilet	14.91	SD-2	300	ED-1	600	-300	
Main Corridor + Lobby	224.80	SD-3	2,600	RD-3	1,200	1,400	
Security & Safety	21.30	SD-2	350	RLBG-2	250	100	
Wait Female	16.39	SD-2	350	RLBG-2	250	100	
Toilet			0	ED-2	200	-200	
Toilet			0	ED-2	200	-200	
623			12,200		9,600	2,600	Positive (+)