Wood Pile-to-Beam **Connections**

HOME BUILDER'S GUIDE TO COASTAL CONSTRUCTION

Technical Fact Sheet No. 3.3

Purpose: To illustrate typical wood pile-to-beam connections, provide basic construction quidelines on various connection methods, and show pile bracing connection techniques.

Key Issues

- Verify pile alignment and correct, if necessary, before making connections.
- Carefully cut piles to ensure required scarf depths.
- Limit cuts to no more than 50 percent of pile cross section.
- Use corrosion-resistant connectors and fasteners such as those fabricated from stainless steel, or connectors and fasteners with corrosion protection such as provided by hot-dip galvanized coating (see Fact Sheet No. 1.7, Coastal Building Materials).
- Accurately locate and drill bolt holes.
- Field-treat all cuts and holes to prevent decay.
- Use sufficient pile and beam sizes to allow proper bolt edge distances.

Built-up beams should be designed as continuous members and not be broken over the piles. Some

homebuilders are using engineered wood products, such as glued laminated timber and parallel strand lumber, which can span longer distances without splices. The ability to span longer distances without splices eases installation and reduces fabrication costs.

> Note: Pile-to-beam connections must be designed by an engineer.




rest on pile.

Pile-to-beam connections must:

- 3. Maintain beam in an upright position.
- 4. Be capable of resisting lateral loads (wind and seismic).


1. Provide required bearing area for beam to

5. Be constructed with durable connectors and fasteners from corrosion-resistant materials or with corrosion protection in accordance with minimum requirements of the International Residential Code. The level of corrosion protection that can be expected will vary depending on the type of wood treatment and fastener type. Make sure the fastener is compatible with the wood variety selected for construction.





3.3: WOOD PILE-TO-BEAM CONNECTIONS




Problem: misaligned piles—some piles are shifted in or out from their intended (design) locations.

There are five possible solutions to fix the problem. (See figure 3 and details in figure 4):


- **Option 1 –** beam cannot be shifted.
- Option 2 beam can be shifted laterally and remains square to building.
- Option 3 beam can be shifted laterally, but does not remain square to building.

Option 4 (not shown) – beam cannot be shifted, and connections shown in this fact sheet cannot be made; install and connect sister piles; an engineer must be consulted for this option.

Option 5 (not shown) – beam cannot be shifted, and connections shown in this fact sheet cannot be made; remove and reinstall piles, as necessary.




Note: Pile-to-beam connections must be designed by an engineer.



Connections to misaligned piles (see drawings on figure 3 and details above)

- 1. The ability to construct the pile-to-beam connections designed by the engineer is directly dependent upon the accuracy of pile installation and alignment.
- 2. Misaligned piles will require the contractor to modify pile-to-beam connections in the field.
- 3. Badly misaligned piles will require removal and reinstallation, sister piles, or special connections, all to be determined by the engineer.

3.3: WOOD PILE-TO-BEAM CONNECTIONS



Note: Pile-to-beam connections must be designed by an engineer.

Additional Resources

American Wood Council (AWC) (http://www.awc.org)

American Institute of Timber Construction (AITC) (http://www.aitc-glulam.org)



Developed in association with the National Association of Home Builders Research Center

3.3: WOOD PILE-TO-BEAM CONNECTIONS