DEMO SEQUENCING NOTES

- 1. INSTALL INTERIOR LVL
- 2. INSTALL HELIFIX TIES INTO MASONRY
- 3. CUT LOCAL OPENINGS IN EXTERIOR WALL TO SLIDE JOISTS INTO. SLIDE IN JOISTS.
- 4. CONNECT JOISTS TO INTERIOR LVL

