


NOTE:

1. U/S EQUIPMENT ELEVATION TAKEN AS 0'-00"
2. TOP OF TRENCH FLOOR ELEVATION IS -4'-00"
3. MAX PLATE SPAN TO BE 3'.
4. MAX PLATE WIDTH TO BE 2'.
5. PL. THICKNESS MAX 3/8"
6. ALL BEAMS ARE W6x15 (SUBJECT TO CHANGE DURING DETAILED DESIGN)
7.  ELECTRICAL EQUIPMENT
8. TRENCH WALLS TO BE 8".
9. HSS 3x3x0.125 POSTS SHALL HAVE A MAX SPACING OF 15'.
10. BASE PL. TO BE 5"x5"x1/4"