

Test Summary

Load, psf	Strain	Void Ratio	t ₅₀ , min	C _v , ft ² /day
100	0.00	0.51	0.00	N/A
500	0.41	0.51	1.00	0.40
1000	0.90	0.50	6.25	0.06
2000	1.36	0.49	3.06	0.13
4000	0.58	0.50	2.72	0.15
8000	1.08	0.49	1.00	0.39
16000	2.06	0.48	0.81	0.48
32000	3.35	0.46	1.44	0.26
8000	3.01	0.47	1.00	0.37
2000	2.65	0.47	4.00	0.09
500	2.19	0.48	N/A	N/A

	Initial	Final
Moisture Content, %	19.0	17.4
Wet Density, pcf	44.5	131.3
Dry Density, pcf	37.4	111.8